

CLEAR GLAZING OPERABLE IN TYPICAL PREFINISHED VINYL WINDOW FRAME

TYPICAL PREFINISHED VINYL WINDOW FRAME SECURED AT NAILING FLANGE (BY POLYTECH)

LOW EXPANSION FOAM (BY OTHER)

Nail Flange

FASTENER

Exterior wall

METAL BRICK TIE (GALV) up to installer not Polytech depending on wall system

RAIN SCREEN

TYVEK AIR BARRIER INSTALLED TO MANUFACTURERS SPECS

TYPICAL 7/16" OSB WALL SHEATHING

R12 TYPE PINK BATT INSULATION (R1215SX)

(TYPICAL) # 8 SELF-TAPPING MACHINE SCREW (BY POLYTECH)

METALIC INSTALLATION CLIP GALVANIZED STEEL- 29MM X 102MM (BY POLYTECH)

(TYPICAL) WOOD WINDOW CASING (BY OTHER)


2X4 LUMBER

6 MIL APPROVED VAPOR BARRIER INSTALLED AS PER NBCC

1/2" GYPSUM WALL BOARD

EXTERIOR

INTERIOR



SCALE

NOTES:

TITLE:

WINDOW INSTALLATION DETAILS

CLIENT:

POLYTECH PRODUCTS LTD.

PROJECT:

**41 WILLIAMS AVENUE
DARTMOUTH, NOVA SCOTIA**

DATE: PROJECT #:

JUNE 2009 09 - 1250

SCALE: FIGURE #:

1:2 3

DRAWN BY:

RC

CHECKED BY:

JF